

Trading Off Diversity and Quality in Natural Language Generation

Hugh Zhang^{*12} Daniel Duckworth^{*1} Daphne Ippolito¹³ Arvind Neelakantan⁴

Abstract

For open-ended language generation tasks such as storytelling and dialogue, choosing the right decoding algorithm is critical to controlling the tradeoff between generation *quality* and *diversity*. However, there presently exists no consensus on which decoding procedure is best or even the criteria by which to compare them. We address these issues by casting decoding as a multi-objective optimization problem aiming to simultaneously maximize both response quality and diversity. Our framework enables us to perform the first large-scale evaluation of decoding methods along the entire quality-diversity spectrum. We find that when diversity is a priority, all methods perform similarly, but when quality is viewed as more important, the recently proposed nucleus sampling (Holtzman et al., 2019) outperforms all other evaluated decoding algorithms. Our experiments also confirm the existence of the ‘likelihood trap’, the counter-intuitive observation that high likelihood sequences are often surprisingly low quality. We leverage our findings to create and evaluate an algorithm called *selective sampling* which tractably approximates globally-normalized temperature sampling.

1. Introduction

Generative language models are applicable for a wide variety of tasks including writing articles, composing Shakespearean sonnets, or engaging in conversation. For nearly all of these goals, human judgments are the sole way to credibly evaluate the quality of the generated text, rendering it prohibitively expensive to optimize directly over the desired objectives. Researchers typically address this issue by adopting a two-stage process. At train time, models seek to imitate a human-written text corpus as a proxy for the true




Figure 1. The Likelihood Trap. We asked 146 crowdworkers to rate the quality of 100 sentences across a variety of model likelihoods. While model log likelihoods are generally positively correlated with average human quality judgments, we notice an inflection point after which they become negatively correlated. Each point in the graph represents the average crowdworker rating of 5 sentences with similar model likelihoods. We discuss this phenomenon in more depth in Section 3.

objective (e.g. higher quality samples). At inference time, models generate text sequences via a decoding algorithm that better optimizes the desired success criteria given the original predictions from the network. Nearly all major breakthroughs in image and language generation over the past few years (Radford et al., 2019; Zhang et al., 2019; Fan et al., 2018) have adopted this two stage process where the model probability distributions differ between train and inference time.

This work examines decoding methods for language models, which are well known to be critical for performance in language generation (Ippolito et al., 2019a). Recent efforts for improving generative language models have focused primarily on altering the model architecture (Vaswani et al., 2017; Gehring et al., 2017), training method (de Masson d’Autume et al., 2019) and model size (Radford et al., 2019; Adiwardana et al., 2020). While effort has also been made towards improving decoders (Vijayakumar et al., 2016; Li & Jurafsky, 2016; Ippolito et al., 2019b), there has been significantly less progress towards evaluating improvements in decoder performance, especially for open-ended

^{*}Equal contribution ¹Google Brain ²Stanford University ³University of Pennsylvania ⁴OpenAI. Correspondence to: Hugh Zhang <hughz@stanford.edu>, Daniel Duckworth <duckworthd@google.com>.

generative tasks where successful models must generate a *diverse* spectrum of high *quality* answers rather than merely a single output.

For many tasks, these two criteria of quality and diversity are not always equally important. In machine translation, the most important criteria is to produce an accurate, high quality translation of the input; generating a variety of alternative translations is also useful, but not if it comes at the cost of correctness. Meanwhile, in open domain dialogue the goal is often to sustain an enjoyable conversation with a human conversational partner and as such, a higher premium is placed on diversity.

To give a concrete example for the case of dialogue, the phrase “I don’t know” is usually a perfectly reasonable remark, and it appears quite often during normal human conversation. However, a chatbot that repeats “I don’t know” on every turn of dialogue makes for a very poor conversationalist. In such open-ended domains, being able to converse about a wide variety of topics with the occasional odd remark is highly preferred to merely repeating the safest possible remark over and over (Li et al., 2016).

To simultaneously capture both of these criteria, we propose framing the goal of generative language models as a multi-objective optimization over both *quality* and *diversity*. The proposed framework is flexible enough to encompass tasks that traditionally place low emphasis on diversity such as machine translation or summarization and others with high diversity such as storytelling.

Furthermore, the proposed framework enables us to evaluate existing decoding algorithms by comparing their performance along the entire quality-diversity spectrum. We compare a variety of commonly-used decoding algorithms in the first large-scale study of decoder quality, utilizing over 38,000 ratings on almost 10,000 samples. We find that when diversity is highly valued, all decoders perform similarly, but when quality is viewed as more important, the recently proposed nucleus sampling (Holtzman et al., 2019) outperforms all other evaluated decoding algorithms.

Additionally, we use our framework to investigate the commonly held intuition that model likelihood is directly correlated with human quality judgments. First, we explicitly test this belief by measuring the relationship between the quality of a sentence as judged by human raters and its likelihood under a generative model. Our findings confirm the existence of a *likelihood trap*, the counter-intuitive observation that the highest likelihood sentences are of surprisingly low quality, despite a generally positive relationship between model likelihoods and human quality judgments. While this finding has been observed across a wide variety of language generation tasks and models ranging from news generation to machine translation (Cohen & Beck, 2018; Holtzman

et al., 2019), to our knowledge we are the first to explicitly quantify the relationship between the two at all points in the model probability space.

Secondly, we propose and evaluate selective sampling, *selective sampling*, a decoder which emphasizes high probability sentences by drawing samples from the global temperature-adjusted model distribution. While this has traditionally been considered intractable due to the difficulty of computing the partition function, we propose a procedure that uses rejection sampling to directly sample from the desired distribution without explicitly computing the partition function. When evaluating this decoder alongside existing token-by-token decoders, we discover that it performs poorly even when taking the likelihood trap into account, suggesting that local token-by-token decoders may be capable of capturing structure that a global decoder does not.

2. Framework

In this section, we introduce a framework for trading off quality and diversity in language generation. Let $\mathcal{X}$ denote the space of all possible generated sentences. We consider autoregressive language models that decompose the likelihood of a sequence $(x_1, x_2, \dots, x_n) = x_{1:n} \in \mathcal{X}$ token-by-token in a left-to-right fashion (Hamilton, 1994; Sutskever et al., 2014). Specifically, the (conditional) likelihood of the sequence is:

$$p_{\text{model}}(x_{1:n} | c) = \prod_{i=1}^n p_{\text{model}}(x_i | x_{1:i-1}, c) \quad (1)$$

where c is any additional conditioning signal, such as the previous turn of dialogue. Random sampling is the decoding procedure that follows naturally from the factorization of the model’s joint distribution where tokens are sampled one-at-a-time according to the model’s conditional distribution, $p_{\text{model}}(x_i | x_{1:i-1}, c)$. Often p_{model} is not sampled from directly; it is first post-processed by a decoder to bias it toward already high-likelihood tokens.

In the proposed framework, we evaluate the quality of a single sentence $x \in \mathcal{X}$ by asking humans for a quality judgment $HJ(x)$. We can define the quality Q of a model as the expected human “quality” judgment for sentences drawn from it:

$$Q(p) = \mathbb{E}_{x \sim p}[HJ(x)]$$

We measure the diversity of a model via the Shannon entropy H (Shannon, 1948), a diversity metric widely used across many fields beyond computer science including biology, economics, chemistry, and physics. Shannon entropy is

given by:

$$H(p) = -\mathbb{E}_{x \sim p}[\log p(x)]$$

This allows us to define our multi-objective optimization problem as maximizing the following goal G :

$$G(p) = Q(p) + \lambda H(p)$$

where λ is the task-specific measure of the relative importance of diversity and quality. For open-ended tasks such as dialogue that place a premium on variety, decoder performance under large λ is critical. For more closed domain tasks such as summarization or machine translation, performance under smaller λ (including possibly 0) is more important.

Ideally, one would optimize directly over goal G , but its dependence on human judgments makes direct optimization infeasible in practice. Instead, prior works optimize a proxy objective (such as the KL divergence) then employ a decoding algorithm to “warp” model p_{model} post-hoc towards higher values of G .

In the following section, we relate our objective G to existing decoders and investigate a novel decoding algorithm that normalized *globally* across all possible sequences rather than simply token-by-token.

3. Selective Sampling

3.1. The Likelihood Trap

Sequence likelihood is commonly used as a heuristic for selecting high-quality generations. In the extreme, beam search approximates finding the *single* most likely generation $x^* = \arg \max \log p_{\text{model}}(x)$ and is the approach principally adopted in machine translation (Koehn, 2004).

However, prior work has suggested that this assumption of a monotonically positive relationship between sequence likelihood and sequence quality breaks down at the extremes. For example, it is well known in the machine translation and image captioning communities that after a certain point, increasing the beam size *hurts* BLEU scores and other measures of quality (Stahlberg & Byrne, 2019; Koehn & Knowles, 2017; Vinyals et al., 2016). More recently Holtzman et al. (2019) observe similar phenomena for open-ended generation where the highest likelihood sentences degenerate into extreme repetition.

We empirically quantify the relationship between sequence likelihoods and human quality judgments by sub-sampling a large number of context-response pairs representing a wide variety of model log likelihoods. We then request human crowdworkers to rate the quality of each response given the context on a five-point “Terrible”-to-“High Quality” scale.

Figure 1 plots these ratings as a function of $\log p_{\text{model}}$ and confirms that on average the highest quality generations are *not* the most likely. Specifically, we find that response quality is generally positively related with $\log p_{\text{model}}(x)$ up until an inflection point after which it becomes negatively related. In our experiments, this inflection point occurs at $\log p_{\text{model}}(x) = -58.09$. Our findings suggest that while model likelihoods form a good proxy for response quality, naively maximizing over sentence likelihood leads to sub-optimal response quality. We term this phenomenon the *likelihood trap*.

Examples of the likelihood trap can be seen in Table ?? . Text sequences with extremely high likelihood tend to devolve into either extreme repetition or other nonsense, which some have attributed to either model biases (Holtzman et al., 2019) or aberrations in the training data (Ott et al., 2018). We do not examine the underlying causes of the likelihood trap in this paper.

3.2. Global Temperature Sampling

Motivated by our findings that human judgments HJ are positively correlated with model likelihoods for some interval of likelihoods, we investigate whether using $\log p_{\text{model}}$ as a proxy for HJ would lead to a better decoding algorithm. Specifically, we create a proxy quality function,

$$\hat{Q}(p) = \mathbb{E}_{x \sim p} \begin{cases} \log p_{\text{model}}(x), & \text{if } \log p_{\text{model}} < \alpha. \\ -\infty, & \text{otherwise.} \end{cases}$$

where α is selected as a hyperparameter.

Using globally-normalized temperature sampling, we can then approximate optimizing for G through instead optimizing for the proxy objective $\hat{G}(p) = \hat{Q}(p) + H(p)$. This is due to the following proposition.

Proposition 1. *Let p be a probability distribution over some finite set $\mathcal{X}$. Let H be the Shannon entropy function. The probability distribution Q which minimizes the reverse KL Divergence $D_{KL}(Q \parallel P)$ subject to $H(Q) = K$ for any achievable constant K has the form,*

$$Q(x) = \frac{P(x)^{1/\tau}}{\sum_{x \in \mathcal{X}} P(x)^{1/\tau}}$$

for some temperature $\tau \in [0, 1]$.

Proof. Proof included in Appendix A.1 □

When applied to autoregressive models, global temperature sampling is usually dismissed as intractable due to the need to sum over the exponentially large space of all possible sequences in pursuit of the partition function $Z = \sum_x p_{\text{model}}(x \mid c)^{1/\tau}$. Instead, past work typically

Context	Response	$\log p(x)$	Classification
The Atlanta Falcons have started the 2015 season 4-0 under new head coach Dan Quinn. Quarterback Matt Ryan has the ...	... mental Tough O'Rourke Tough apology assessment category of virtue from Boser' Blog here. It's got letters and images on it and is utterly ...	-177	Nonsense
	... team afloat and looks closer to the 2010 Atlanta Falcons. Starting cornerback Desmond Trufant was one of the top players on the 2014 ...	-74	Reasonable
	... team in the thick of the NFC South race. The Atlanta Falcons have started the 2015 season 4-0 under new head coach Dan Quinn. Quarter...	-14	Repetition
They have changed the phone menu to try to deflect us to email, but you can still get a live ...	... answer from a female administratoria llallushoss@rahpx Sandra PJ Jenniea nightiopq HamidF daroyqg S') ...	-229	Nonsense
	... message or call on line, so I suppose they are just using that as an excuse. Yet they are still telling people to change their telephone number...	-86	Reasonable
	... link to a phone number here. They have changed the phone menu to try to deflect us to email, but you can still get a live link to...	-23	Repetition

Table 1. Examples of sentences at various model likelihoods. Sentences with very low $\log p_{\text{model}}$ generate **nonsense**, while sentences that have high likelihood under the model often devolve into extreme **repetition**. Nonsense and repetition classifications shown here are only for illustrative purposes. Crowdworkers simply rated sentences for overall quality. See Appendix for more details.

decomposes sentences into tokens in a left-to-right autoregressive fashion and then use a local approximation,

$$\hat{Z} = \prod_{i=1}^n \sum_{x_i} p_{\text{model}}(x_i | x_{1:i-1}, c)^{\frac{1}{\tau}}$$

where models are normalized locally over each set of tokens. This results in the well known (local) temperature sampling algorithm.

Unfortunately, while replacing the global partition function with a series of local ones transforms an exponential problem into a linear one, this approximation may bias the model towards favoring local structure over global structure. Indeed, we show via the following example that for some joint distributions, it is *impossible* to represent globally-normalized temperature sampling via local temperature sampling, even if local temperature sampling is allowed to use a different temperature τ at each timestep.

Proposition 2. *There exists a probability distribution p and global temperature τ such that no choice of parameter allows local temperature sampling to match the joint distribution $p(x)^{1/\tau}$.*

Proof. Figure 2 illustrates one such choice of p . By construction, local temperature sampling is forced to set $p_{\text{local}}(A) = p_{\text{local}}(B)$ regardless of the temperature hyperparameter used at that timestep. Setting a global temperature of $\tau = 0.5$ results in

$$P(A) = \frac{0.1^2 + 0.4^2}{0.1^2 + 0.4^2 + 0.25^2 + 0.25^2} = 0.5763$$

$$P(B) = \frac{0.25^2 + 0.25^2}{0.1^2 + 0.4^2 + 0.25^2 + 0.25^2} = 0.4237$$

which is not imitable by any local temperature setting. $\square$




Figure 2. Any choice of temperature for local temperature sampling must have $P(A) = P(B)$. However, choosing global temperature $\tau = 0.5$ results in $P(A) = 0.5763$ and $P(B) = 0.4237$ which is impossible for any choice of local temperatures to satisfy.

Our core insight is that one can sample from the globally-normalized temperature sampling distribution without estimating the partition function Z via rejection sampling. Rejection sampling (Forsythe, 1972) gives an algorithm from sampling from an (unnormalized) energy distribution p_{energy} if there exists a proposal distribution q and constant M such that $Mq \geq p_{\text{energy}}$.

We observe that $p_{\text{model}} > p_{\text{model}}^{\frac{1}{\tau}}$ for $\tau \in (0, 1)$ and $0 \leq p \leq 1$. This allows us to use p_{model} as the proposal distribution since the unnormalized probabilities of the global temperature sampling are given by $p_{\text{global}} \propto p_{\text{model}}^{\frac{1}{\tau}}$.

Selective sampling, by design, significantly increases the chances of sampling sequences with large values of $\log p_{\text{model}}$. To avoid falling into the likelihood trap,

Algorithm 1 Selective Sampling

Require: Global temperature τ , Cutoff α , and p_{model} .
 Set $M = \alpha^{\frac{1}{\tau}-1}$
while more sequences are required **do**
 Sample a sequence x from p_{model} .
 if $\log p_{\text{model}}(x) > \alpha$ **then**
 Reject sample
 else
 Accept with probability $\frac{p_{\text{model}}(x)^{\frac{1}{\tau}-1}}{M}$
 end if
end while

we propose explicitly discarding generations x where $\log p_{\text{model}}(x)$ is greater than a chosen hyperparameter α . An additional positive side effect of the cutoff is that the envelope constant M can be chosen to create a tight bound on p_{energy} , which increases acceptance probabilities by several orders of magnitude.

A priori, it is not obvious how to choose α effectively. We propose collecting human judgments for a selection of random samples from p_{model} as illustrated in Figure 1 and setting α equal to the discovered inflection point. Note, that while this results in our procedure ignoring the set of sentences that individually have the highest probabilities, the total probability mass of this set is quite low: less than 0.5% in our experiments.




Figure 3. Histogram over $p_{\text{model}}(x)$ for samples drawn from the same prompt. 99.5% of samples have log likelihood less than the chosen cutoff α shown in black.

4. Experiments

In Section 2, we introduce a theoretical framework for comparing decoding algorithms along a quality-diversity curve. Under this framework, we evaluate several commonly used decoding algorithms in a human study described below. In addition to selective sampling, we consider the following autoregressive decoding algorithms,

- **temperature:** Sample tokens with probability proportional to $p_{\text{model}}(x_i|x_{1:i-1})^{1/t}$. t varies from 0 to 1.
- **top- k** (Fan et al., 2018): Sample tokens only from the top- k highest likelihood tokens in the vocabulary at each timestep. k varies from 1 to vocabulary size.
- **top- p** (also known as nucleus sampling) (Holtzman et al., 2019): Sample only from tokens comprising the top- p percent of probability mass at each timestep, as ordered from most to least likely. p varies from 0 to 1.

At the extremes of their hyperparameter ranges, these algorithms all converge to greedy decoding and random sampling, respectively. To sweep across the quality-diversity curve, we consider several hyperparameter settings per decoding algorithm below. We refer to each decoding algorithm-hyperparameter combination as a ‘decoding configuration’.

4.1. Setup

We apply each decoding algorithm to the 774M parameter variant of GPT-2 (Radford et al., 2019), a publicly-released language model. To ground samples in a common context, we select a set of 48 examples from the GPT-2 test set to condition upon. As samples are evaluated by human raters, we filter out examples containing explicit content or web markup. Samples are drawn by conditioning on a ‘prompt’ consisting of the first 20 space-delimited words of a test example. As sample quality becomes ambiguous when samples are terse (Ippolito et al., 2019a), we explicitly require all sampling methods to generate exactly 30 tokens, a length approximately equal to the prompt.

To estimate the expected Human judgment score $\mathbb{E}_p[HJ(x)]$ of the probability distributions induced by each decoding algorithm, we enlist a qualified pool of 146 Amazon Mechanical Turk (AMT) workers selected by satisfactory performance on a qualification task. Workers are presented sets of five samples, each conditioned on the same prompt and drawn from five different algorithm-hyperparameter configurations and asked to assign qualitative scores to each sample ranging from human-like to gibberish. The exact prompts, as shown to crowdworkers, are included in the Appendix.

Prior work has found that human annotators have significant trouble in directly separating out machine and human generated responses when they are of similar quality, as the task of assessing sentence quality is highly subjective (Ippolito et al., 2019a). We found that constructing pairwise preference ratings by randomly pairing samples evaluated at the same time significantly reduced the variance of our results. Specifically, if one sample is rated higher than the other, one is assigned a score of +1 and the other -1. If both

are rated equally, both are assigned a score of 0. The score assigned to a decoding configuration is its average score across all pairwise preference ratings. The average scores for each decoding strategy setting we experimented with are shown in Figure 6.

4.2. Results

We now introduce the first large-scale study comparing decoding algorithms and their hyperparameters. Unlike all prior work (Holtzman et al., 2019; Ippolito et al., 2019b), we explicitly put decoding algorithms *on equal footing* by comparing sample quality at equal points of diversity. We consider five hyperparameter configurations per decoding algorithm for a total of twenty decoding algorithm-hyperparameter configurations. For each configuration and prompt, we draw ten samples. In total, workers rate nearly 10,000 samples resulting in over 38,000 paired ratings.




Figure 4. Human judgment scores as a function of decoding algorithm’s entropy. Each point represents a single choice of decoding algorithm and hyperparameter. Error bars represent 95% bootstrap confidence intervals.

Our main results are summarized in Figures 4 and 5. We empirically estimate the entropy of the probability distribution induced by each decoding configuration. Reassuringly, both entropy and human judgment scores vary smoothly with decoding algorithm hyperparameter.

As expected, random sampling directly from the model $p_{\text{model}}(x)$ is simultaneously the highest entropy *and the lowest quality*. This is empirically consistent with the long-standing intuition that decoding algorithms are critical to improving sample quality. Why are samples from random sampling such poor quality? Language models such as GPT-2 are trained to minimize the KL-divergence between a training set and the model distribution p_{model} , an objective that prioritizes recall over precision (Arjovsky et al., 2017). As a result, models tend to ensure that high quality sequences have high likelihood without insisting that all high likelihood sequences also have high quality. When

we evaluate samples from the model, we evaluate the latter condition.

Our second conclusion is that sample quality varies significantly with entropy for all decoding algorithms. Moreover, when aligned on entropy, sample quality between all autoregressive decoding algorithms is comparable across a wide range. It is only when entropy is low – when decoding algorithms heavily influence sampling – that sample quality between algorithms diverge. In this regime, we find that nucleus sampling outperforms top- k , which in turn outperforms temperature sampling. Observing such a difference should be unsurprising: the entropy of a distribution alone does not determine its sample quality. We conclude that a fair comparison of decoding algorithms must not only compare at the same level of entropy but at a *range* of entropy levels.

Finally and most surprisingly, we find that, in spite of its theoretical appeal, selective sampling consistently underperforms all other decoding algorithms considered.

4.3. Selective Sampling

Why does selective sampling underperform? Our error analysis yields at least two potential causes: priors induced by decoding algorithms and a context-dependent likelihood trap. We first consider the implicit priors of autoregressive decoding algorithms. Autoregressive decoding algorithms naturally favor sequences x where each token x_i has high model likelihood with respect to its conditional distribution $p_{\text{model}}(x_i | x_{1:i-1})$. Note that this is not necessarily the same as favoring *all* high-likelihood sequences with high joint likelihood $p_{\text{model}}(x)$; a criteria selective sampling targets at low temperatures. We hypothesize that autoregressive decoding algorithms are inducing additional structure beyond high joint likelihood.

To test this hypothesis, we construct a human rating experiment that pairs random samples from a decoding algorithm with another random samples from the model distribution p_{model} such that the two samples have the *same joint sentence likelihoods*. In this way, we are able to control for differences in the distribution of p_{model} that different decoders induce and explicitly test only how various decoding algorithms promote different sequences with the same overall joint likelihood. We draw samples from three commonly-used decoding configurations conditioned on all 48 prompts and compare each against random sampling by ask crowdworkers to rate which of the paired responses is of higher quality.

In Figure 6, we see that temperature sampling with $t = 0.7$ is undeniably preferred to otherwise equivalent samples drawn directly from p_{model} , though for other decoding configurations, the difference is currently less clear. Selective




Figure 5. Human judgment scores for each decoding algorithm and hyperparameter choice. "Selective" is selective sampling and "model" is sampling directly from the probability distribution outputted by the language model. A score of 0 represents no preference. Selective sampling underperforms other more computationally efficient strategies.




Figure 6. Human judgment scores for paired samples of equal log likelihood. 95% bootstrap confidence intervals. Dotted line represents random judgments. For all decoding strategies it can be seen that decreasing diversity tends to lead to higher-judged outputs.




Figure 7. Distribution of prompt-conditional sample log likelihoods for five different prompts. The dotted-line represents the cutoff α used in experiments.

sampling, a method with proposals drawn from p_{model} , does not share this prior of its autoregressive locally normalized decoding counterparts. We can thus conclude that the success of a decoding algorithm involves more than promoting high joint likelihood; in this way, selective sampling is deficient.

Second, we consider the distribution over sample log likelihoods conditioned on a fixed prompt as show in Figure 7. Depending on the prompt, the distribution over log likelihoods varies from prompt to prompt. In selective sampling, we’ve elected to choose a single, global maximum likelihood constant α . For some prompts, this has nearly no impact – nearly all samples have likelihood below the cutoff. For others, this may eliminate nearly half of samples, leaving only those of lower quality. This suggests that a fixed cutoff α for all prompts may not be ideal.

Based on the prior experiments, we find that choice of decoding algorithm and its hyperparameter has a significant impact on sample quality and diversity. Further, we find

that sample quality and diversity can be traded for one another, and that the merit of a decoding algorithm requires comparing it to others at equivalent levels of diversity. We also given evidence that autoregressive decoding algorithms induce additional preference beyond promoting samples with high joint likelihood; a beneficial preference selective sampling does not share.

5. Related Work

Encouraging Diversity Several recent work have proposed strategies for increasing the diversity of text generated by language models. These approaches fall into two broad categories: (1) algorithmic changes to the decoding algorithm and (2) methods that involve training auxiliary language models or modifying the training paradigm for the main language model in some way.

The advantage of changing the decoding algorithm is that

improvements can be rapidly be implemented on top of any already trained language model. Vijayakumar et al. (2016), Li & Jurafsky (2016), Tam et al. (2019), and Kulikov et al. (2018) all propose modifications to beam search to force it to explore a more diverse set of beams. In contrast, modifications to random sampling that have been proposed aim to reduce diversity and thereby increase quality (Fan et al., 2018; Holtzman et al., 2019). Ippolito et al. (2019b) compare many of these algorithmic advancements on the tasks of open-ended dialog and image captioning, concluding that the quality-diversity tradeoff makes it nearly impossible to say that any one of these methods is ubiquitously best.

We choose to evaluate three commonly used decoding methods: nucleus sampling (Holtzman et al., 2019), top-k sampling (Fan et al., 2018), and temperature sampling. All three of these methods control the relative tradeoff between quality and diversity with a single hyperparameter. Top-k sampling samples from only the top-k most likely tokens at a timestep, proportionally according to the original probability. Nucleus sampling (also called top-p) sampling operates similarly, but chooses an adaptive k such that the top-k tokens comprise of the top-p percent of the total probability mass at each timestep. Temperature sampling divides the logits of each token by the temperature hyperparameter before normalizing and converting the logits into sampling probabilities. In terms of diversity-promoting approaches that require training new language models, (Li et al., 2016) use a language model that predicts the source sequence given the target sequence to rank candidate generations, penalizing generations that are too generic (have low $P(\text{source} \mid \text{target})$). Welleck et al. (2019) propose a novel loss function which discourages the model from assigning too high probability to repetitive wording. Zhang et al. (2018) and Xu et al. (2018) use adversarial learning methods to encourage diversity. Though these methods are promising, the extra complexity of training makes them less attractive for quickly improving upon existing language models.

The concept of oversampling generations and then ranking them has been popular since the days of statistical machine translation (Shen et al., 2004) but has also been used more recently in other domains (Li et al., 2016; Ippolito et al., 2019b; Kriz et al., 2019). Our particular contribution is to relate our sampling algorithm to the reverse KL divergence and competing objectives maximization. We are also able to use this method to give approximate probability density estimates for sampled sentences, which typically cannot be done for algorithms that oversample generations.

Likelihood Trap We are far from the first to observe evidence of the likelihood trap. In particular, the machine translation and image captioning communities have long known that using higher beam sizes often leads to lower

BLEU scores (Cohen & Beck, 2018; Vinyals et al., 2016; Yang et al., 2018). In open-ended generation, Holtzman et al. (2019) find similar results, observing that maximizing the likelihood generates extremely repetitive sentences. In addition to finding corroborating evidence that low quality generations appear at both the low and high probability extremes, our main contribution towards understanding the likelihood trap is the first explicit measurement of the relationship between model likelihoods and human quality judgments at all points in the model probability space, not just the endpoints.

Ott et al. (2018) attempt to quantify the reasons behind the likelihood trap, proposing that the underlying issue is low quality examples in the training data. They demonstrate that the likelihood trap can be avoided when restricting themselves to a significantly smaller dataset where each training point is carefully examined to guarantee that it is high quality. However, given the recent interest in training increasingly large language models on increasing large datasets, it seems infeasible to guarantee the quality of every example included in the dataset.

Frameworks Note that our framework is related, but not identical to many frameworks such as Hashimoto et al. (2019); Kingma & Welling (2013); Goodfellow et al. (2014) which ask that generative models mimic the training distribution exactly. While some tasks do require indistinguishability as the ultimate goal (e.g. representation learning (Bengio et al., 2013), Turing Test (Turing, 2009; Ippolito et al., 2019a), etc.), this is typically not the case for most generation tasks. Humans make errors, but a “perfect” model would not seek to imitate these mistakes. Because we ground quality evaluations in human judgments rather than on any statistical measure, our framework is easily able to capture the possibility of superhuman performance in ways that frameworks based solely on a statistical divergence would find difficult.

6. Conclusion

In this paper, we propose a framework for credibly evaluating decoding algorithms and use it to conduct the first large scale evaluation of decoding algorithms by measuring their performance along the entire quality-diversity frontier. Our findings suggest that existing decoding algorithms are more or less interchangeable in high diversity settings, but that nucleus sampling performs best when quality is valued over diversity. Additionally, we provide evidence for the existence of a *likelihood trap* and are the first to explicitly measure the relationship between $\log p_{\text{model}}$ and human judgments. Finally, we propose and evaluate selective sampling, the first algorithm that can tractably estimate *globally* normalized temperature sampling.

In the future, we hope to extend our work to additional generative language models as well as other modalities such as image and music generation. Additionally, we leave questions of whether selective sampling can be improved via choice of an adaptive cutoff that can vary based on the prompt or proposal distributions other than random sampling for future discovery.

References

- Adiwardana, D., Luong, M.-T., So, D. R., Hall, J., Fiedel, N., Thoppilan, R., Yang, Z., Kulshreshtha, A., Nemade, G., Lu, Y., et al. Towards a human-like open-domain chatbot. *arXiv preprint arXiv:2001.09977*, 2020.
- Arjovsky, M., Chintala, S., and Bottou, L. Wasserstein gan. *arXiv preprint arXiv:1701.07875*, 2017.
- Bengio, Y., Courville, A., and Vincent, P. Representation learning: A review and new perspectives. *IEEE transactions on pattern analysis and machine intelligence*, 35(8): 1798–1828, 2013.
- Cohen, E. and Beck, J. C. (unconstrained) beam search is sensitive to large search discrepancies. 2018.
- de Masson d’Autume, C., Mohamed, S., Rosca, M., and Rae, J. Training language gans from scratch. In *Advances in Neural Information Processing Systems*, pp. 4302–4313, 2019.
- Fan, A., Lewis, M., and Dauphin, Y. Hierarchical neural story generation. *arXiv preprint arXiv:1805.04833*, 2018.
- Forsythe, G. E. Von neumann’s comparison method for random sampling from the normal and other distributions. *Mathematics of Computation*, 26(120):817–826, 1972.
- Gehring, J., Auli, M., Grangier, D., Yarats, D., and Dauphin, Y. N. Convolutional sequence to sequence learning. In *Proceedings of the 34th International Conference on Machine Learning-Volume 70*, pp. 1243–1252. JMLR. org, 2017.
- Goodfellow, I. J., Pouget-Abadie, J., Mirza, M., Xu, B., Warde-Farley, D., Ozair, S., Courville, A., and Bengio, Y. Generative adversarial nets. In *Advances in Neural Information Processing Systems (NeurIPS)*, 2014.
- Hamilton, J. D. *Time series analysis*, volume 2. Princeton New Jersey, 1994.
- Hashimoto, T. B., Zhang, H., and Liang, P. Unifying human and statistical evaluation for natural language generation. *arXiv preprint arXiv:1904.02792*, 2019.
- Holtzman, A., Buys, J., Forbes, M., and Choi, Y. The curious case of neural text degeneration. *arXiv preprint arXiv:1904.09751*, 2019.
- Ippolito, D., Duckworth, D., Callison-Burch, C., and Eck, D. Human and automatic detection of generated text. *arXiv preprint arXiv:1911.00650*, 2019a.
- Ippolito, D., Kriz, R., Kustikova, M., Sedoc, J., and Callison-Burch, C. Comparison of diverse decoding methods from conditional language models. *arXiv preprint arXiv:1906.06362*, 2019b.
- Kingma, D. P. and Welling, M. Auto-encoding variational bayes. *arXiv preprint arXiv:1312.6114*, 2013.
- Koehn, P. Pharaoh: a beam search decoder for phrase-based statistical machine translation models. In *Conference of the Association for Machine Translation in the Americas*, pp. 115–124. Springer, 2004.
- Koehn, P. and Knowles, R. Six challenges for neural machine translation. *arXiv preprint arXiv:1706.03872*, 2017.
- Kriz, R., Sedoc, J., Apidianaki, M., Zheng, C., Kumar, G., Miltsakaki, E., and Callison-Burch, C. Complexity-weighted loss and diverse reranking for sentence simplification. *arXiv preprint arXiv:1904.02767*, 2019.
- Kulikov, I., Miller, A. H., Cho, K., and Weston, J. Importance of a search strategy in neural dialogue modelling. 2018.
- Li, J. and Jurafsky, D. Mutual information and diverse decoding improve neural machine translation. 2016.
- Li, J., Galley, M., Brockett, C., Gao, J., and Dolan, W. B. A diversity-promoting objective function for neural conversation models. pp. 110–119, 2016.
- Ott, M., Auli, M., Grangier, D., and Ranzato, M. Analyzing uncertainty in neural machine translation. *arXiv preprint arXiv:1803.00047*, 2018.
- Radford, A., Wu, J., Child, R., Luan, D., Amodei, D., and Sutskever, I. Language models are unsupervised multitask learners. *OpenAI Blog*, 1(8):9, 2019.
- Shannon, C. E. A mathematical theory of communication. *Bell system technical journal*, 27(3):379–423, 1948.
- Shen, L., Sarkar, A., and Och, F. J. Discriminative reranking for machine translation. pp. 177–184, 2004.
- Stahlberg, F. and Byrne, B. On NMT search errors and model errors: Cat got your tongue? In *Proceedings of the 2019 Conference on Empirical Methods in Natural Language Processing and the 9th International Joint Conference on Natural Language Processing (EMNLP-IJCNLP)*, pp. 3356–3362, Hong Kong, China, November 2019. Association for Computational Linguistics. doi: 10.18653/v1/D19-1331. URL <https://www.aclweb.org/anthology/D19-1331>.

- Sutskever, I., Vinyals, O., and Le, Q. V. Sequence to sequence learning with neural networks. In *Advances in neural information processing systems*, pp. 3104–3112, 2014.
- Tam, Y.-C., Ding, J., Niu, C., and Zhou, J. Cluster-based beam search for pointer-generator chatbot grounded by knowledge. In *Dialog System Technology Challenges 7 at AAAI 2019*, 2019.
- Turing, A. M. Computing machinery and intelligence. In *Parsing the Turing Test*, pp. 23–65. Springer, 2009.
- Vaswani, A., Shazeer, N., Parmar, N., Uszkoreit, J., Jones, L., Gomez, A. N., Kaiser, Ł., and Polosukhin, I. Attention is all you need. In *Advances in neural information processing systems*, pp. 5998–6008, 2017.
- Vijayakumar, A. K., Cogswell, M., Selvaraju, R. R., Sun, Q., Lee, S., Crandall, D., and Batra, D. Diverse beam search: Decoding diverse solutions from neural sequence models. 2016.
- Vinyals, O., Toshev, A., Bengio, S., and Erhan, D. Show and tell: Lessons learned from the 2015 mscoco image captioning challenge. *IEEE transactions on pattern analysis and machine intelligence*, 39(4):652–663, 2016.
- Welleck, S., Kulikov, I., Roller, S., Dinan, E., Cho, K., and Weston, J. Neural text generation with unlikelihood training. *arXiv preprint arXiv:1908.04319*, 2019.
- Xu, J., Ren, X., Lin, J., and Sun, X. Diversity-promoting gan: A cross-entropy based generative adversarial network for diversified text generation. In *Proceedings of the 2018 Conference on Empirical Methods in Natural Language Processing*, pp. 3940–3949, 2018. URL <https://www.aclweb.org/anthology/D18-1428>.
- Yang, Y., Huang, L., and Ma, M. Breaking the beam search curse: A study of (re-) scoring methods and stopping criteria for neural machine translation. *arXiv preprint arXiv:1808.09582*, 2018.
- Zhang, Y., Galley, M., Gao, J., Gan, Z., Li, X., Brockett, C., and Dolan, B. Generating informative and diverse conversational responses via adversarial information maximization. In *Advances in Neural Information Processing Systems*, pp. 1815–1825, 2018.
- Zhang, Y., Sun, S., Galley, M., Chen, Y.-C., Brockett, C., Gao, X., Gao, J., Liu, J., and Dolan, B. Dialogpt: Large-scale generative pre-training for conversational response generation. 2019.

A. Appendix

A.1. Proof of Proposition 1

Notice first that, subject to $H(Q) = K$,

$$\arg \min_Q D_{KL}(Q \parallel P) = \arg \max_Q \sum_{x \in X} Q(x) \log P(x)$$

Properly choosing K^* allows us to write the Lagrangian dual for the above constrained optimization problem as

$$L(Q, \lambda, \mu) = \lambda \left(\sum_{x \in \mathcal{X}} Q(x) \log P(x) \right) - K^* \quad (2)$$

$$+ H(Q) + \mu \left(\left(\sum_{x \in \mathcal{X}} Q(x) \right) - 1 \right) = 0 \quad (3)$$

For any $x \in \mathcal{X}$

$$\begin{aligned} & \nabla_{Q(x)} L(Q, \lambda, \mu) \\ &= \lambda \log P(x) + \log Q(x) + 1 + \mu = 0 \\ \Rightarrow Q(x) &= \frac{P(x)^{-\lambda}}{e^{1+\mu}} \end{aligned}$$

Setting $\lambda = -\frac{1}{\tau}$ and $\mu = -1 + \log \sum_{x \in \mathcal{X}} P(x)^{\frac{1}{\tau}}$ immediately gives us temperature sampling. Finally, observing that positive temperatures give us the local maxima and negative temperatures give us the local minima completes the proof.

A.2. Experimental Design

In this section, we describe the design of experiments presented in Section 4 in greater detail.

We begin by describing the task presented to crowdsourced raters. A sample task is shown in Figure 9. Each task consists of a “context” sequence of the first 20 words in a news article.¹ We then present the rater with five continuations of 30 word-piece tokens. The rater assigns a label of “High Quality”, “Decent”, “Passable”, “Bad” or “Terrible” to each. We note that these labels are inherently subjective, and include a description and reference example before each task to calibrate the rater. The same description and example is repeated in Figure 8.

In preliminary experiments, we found examples and instructions insufficient for achieving repeatable results. Manual inspection of rater responses revealed a failure to interpret the labels correctly as well as spammers who would always choose the same response for every prompt. As a result, we crafted a qualification exam of five continuations. Only raters which rated all five continuations correctly or nearly

correctly² were allowed to participate in further experiments. Of the 550 crowdsourced workers surveyed, 136 met this criteria. We refer to this set of raters as the “qualified rater pool” below.

Even with a qualification exam, we found raters often disagree on the appropriate label for a given continuation. However, when asked to choose which of two continuations was higher quality (if any), raters were better aligned. With this in mind, we choose to analyze *pairs* of ratings given in the same task. From five absolute ratings, we construct twenty pairwise preference ratings: two per pair of continuations. If two continuations receive the same label, they are assigned a preference of 0. If the first continuation is rated higher than the second, the pair (first, second) is assigned a score of +1 and the pair (second, first) a score of -1. All analyses comparing multiple decoding methods use this methodology.

Even with the precautions above, care is needed to ensure repeatable results. To measure this, we performed an “A/A” experiment prior to data collection. This experiment consists of having the same tasks rated by two different pools of raters. Identical analyses are performed on both rating results, and the experimental setup is deemed valid if conclusions are consistent. To achieve this, we constructed 150 tasks³ using a subset of the context sequences and decoding methods from our primary experiment. We artificially split the qualified worker pool in two by sending the same tasks for evaluation at midnight and at noon.⁴ We submit the same set of tasks to both rater pools. An analysis of results from both sets of ratings (Figure 10) reveals a statistically consistent preference of top- p over top- k and (local) temperature sampling, and a severe disapproval of random sampling from the model. These results are also consistent with the same statistics gathered in the full-scale experiment presented in the main text and another experiment described below.

To further validate the reliability of our methodology, we explicitly measure inter-rater agreement on the same set of 150 tasks in a follow-up experiment after large-scale data collection. In this experiment, we ask each task be rated by five distinct raters. We measure Fleiss’s Kappa, a measure inter-rater agreement, on the resulting pairwise ratings. We obtain a score of 0.1964 – an indication that a correlation between raters exists but that the task is far from unambiguous. While this may initially appear concerning, we argue that this is an indication of the task’s difficulty. Unlike image

²Raters which incorrectly labeled at most one continuation with a label at most one level off (e.g. if the correct answer is “Bad”, acceptable errors are “Passable” and “Terrible”) are counted as “nearly correct”.

³The large-scale experiment includes 1,930 tasks.

⁴All tasks within each experiment were rated within 4 hours and 1.5 hours, respectively.

¹News articles are sourced from GPT-2’s WebText dataset. <https://github.com/openai/gpt-2-output-dataset>

Instructions

Below you will find multiple continuations to a given "context" sentence. Please rate the continuations according to their quality.

Notes: High quality continuations tend to **sound like fluent English**. Low quality continuations tend to **repeat, contradict prior statements, or look like text directly copy-pasted from a web page**. Continuations may terminate at ANY time, including in the middle of a word. **DO NOT PENALIZE** for early termination.

We will reject your HIT if you input obviously wrong answers.

Example

Example Context: **LONDON (Reuters) - British Prime Minister Boris Johnson said he would act to stop the early release from prison of convicted terrorists following...**

Quality	Description	Example Continuation
High Quality	Completely plausible, impossible to distinguish from human-written.	...a street attack by an Islamist militant days after he was set free half way through his jail term. Sudesh Amman, jailed in 2018 for...
Decent	Plausible, natural-sounding text, but may contain one or two subtle contradictions or weirdnesses.	...an independent review of the government's animal welfare policies. Britain's Prime Minister Boris Johnson takes part in a...
Passable	Looks plausible at first glance but doesn't make sense. May be entirely off-topic, repetitive, or contain serious contradictions.	...the early release from prison of others. President Trump is quoted, "I strongly believe these convicted terrorists should be convicted..."
Bad	Not a plausible English sentence, contains extreme repetition or web fragments such as "Hide Caption 11" or "Like us on Facebook Twitter."	...a series of public public appeals. Slideshow (3 Images) FILE PHOTO https://www.washingtonpost.com/news/worldview...
Terrible	Not a valid English sentence, gibberish.	... wound' '.Breached KIA, by inter MinurtiSir Clinea490 down to Ot got herg of te-ion (W:

Figure 8. Instructions for the crowdworker task. Each sentence continuation is labeled on a scale from “Terrible” to “High Quality”. A description of each label and an example continuation that fits each each is provided before each task.

classification, for example, a universally agreeable criteria for text quality does not exist. A measure of Cohen’s Kappa on the A/A experiment above produces a score of 0.19578 – nearly identical to the inter-rater agreement experiment described here. The similarity of these two statistics gives evidence that the proposed experimental design is repeatable in spite of the task’s ambiguity. These results underscore the importance of large-scale, repeatable studies like that presented here.

We conclude by measuring rater preference between each pair of sampling method and hyperparameter on the five-raters-per-task inter-rater agreement experiment described above. Results, as shown in Figure 12, indicate that the same trends presented in the full-scale experiment (Figure 5) hold,

- Top- p is preferred to all other sampling methods,
- Increased diversity correlates with lower human judgement scores, and
- Random sampling directly from the model produces the lowest human judgement scores by a large margin

Given the following context, please rate the next 5 continuations: "Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a "

Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a three-minute video that will try to put a human face on her first days out of the spotlight after accepting the Democratic presidential nomination. Sitting on...	☐ High Quality	☐ Decent	☐ Passable	☐ Bad	☐ Terrible
Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a new ad in which she talks about her time as a first lady and her time as secretary of state. "I've been reflecting on my time...	☐ High Quality	☐ Decent	☐ Passable	☐ Bad	☐ Terrible
Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a new campaign ad that details her time as secretary of state. The ad, which was released by her campaign, features Clinton talking about her time as...	☐ High Quality	☐ Decent	☐ Passable	☐ Bad	☐ Terrible
Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a pair of ads attacking Republican presidential candidate Donald Trump for taking time off from the campaign trail to deal with a terminal illness. Hide Caption 7 of 7...	☐ High Quality	☐ Decent	☐ Passable	☐ Bad	☐ Terrible
Clinton talks about her time of 'reflection' during sick days Hillary Clinton returned to the campaign trail Thursday afternoon, debuting a new television ad that takes a closer look at her hardscrabble childhood. They are of a different color, however. In his childhood,...	☐ High Quality	☐ Decent	☐ Passable	☐ Bad	☐ Terrible

Figure 9. Sample crowdworker task used for the main evaluation results. Raters assign a label on a scale from “Terrible” to “High Quality” to each of five continuations sharing a common context of twenty words. Each continuation is generated by a different sampling method and hyperparameter.




Figure 10. Average Human judgement scores for each sampling method, aggregated across sampling method hyperparameters. In spite of being collected by different raters on different sets of tasks and different points in time, rater preference remains consistent.

Experiment	Num Ratings	Kappa
A/A	2,968	0.1957 (Cohen's)
Five-Rater	14,760	0.1964 (Fleiss's)

Figure 11. Inter-rater agreement between pairwise preference ratings as measured in a preliminary A/A experiment and an explicit, five-raters-per-task inter-rater agreement experiment. While agreement is low, Kappa is strongly consistent between both experiments.




Figure 12. Human judgement scores for each decoding algorithm and hyperparameter choice, as measured in the inter-rater agreement experiment. Preference between sampling methods remains consistent with large-scale experiment shown in Figure 5 in spite of using only decodes generated by a subset of context sequences.